

**SCHEDULE 'A'**

Annexure: I

**Name of work : Making of Kachcha drains and cleaning of open drains/nallahs in Township.**

S.No	It. Code	Description of items	Qty.	Unit	Rate	Amount
1	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1	All kinds of soil.	410.00	CUM	103.40	42394.00
2	1.1	Carriage of material by mechanical transport including loading, unloading and stacking etc. complete				
(a)	1.1.2	Earth				
		(a) upto a lead of 1 km	160.00	CUM	49.42	7907.20
		(b) upto a lead of 3 km	150.00	CUM	63.32	9498.00
		(c) upto a lead of 5 km	100.00	CUM	76.48	7648.00
(b)	1.1.1	Lime, moorum, building rubbish.				
		(a) upto a lead of 1 km	300.00	CUM	39.53	11859.00
		(b) upto a lead of 3 km	200.00	CUM	50.66	10132.00
		(c) upto a lead of 5 km	150.00	CUM	61.19	9178.50
<b>Total Rs. :</b>						<b>98616.70</b>

Percentage quoted by the Contractor	%	Above	Below	At Par
Percentage quoted by the Contractor in words				

Signature of Contractor

Signature of Officer

**SCHEDULE 'A'**

Annexure: II

**Name of work : Making of Kachcha drains and cleaning of open drains/nallahs in Township.**

<b>S.No</b>	<b>It. Code</b>	<b>Description of items</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate quoted by Contractor In Figure &amp; Words</b>
1		Cleaning of storm water drain open/closed of any depth and upto one mt. width in BHEL Township including removal of silt and all vegetation etc. upto full depth complete to the satisfaction of Engineer Incharge and disposal of rubbish/silt within 100 mt. lead and dressing the same. Piplani - 35000 RM Berkhera - 30000 RM Habibganj - 5000 RM Govindpura - 20000 RM ----- 90000 RM	90000.00	RM	
2		Clearing & desilting of Nallah including uprooting all vegetation & removal of boulders/stone metal if any etc. and disposal of the same within 50 mtrs. lead and 1.50 mtrs. lift as per instruction of Engineer Incharge.	13500.00	SQM	

Signature of Contractor

Signature of Officer