

SCHEDULE - "A"**Annexure - II****Name of work : Maintenance of sewerage system in Township.**

S. No	Item	Qty	Departmental Rate per Month (Rs)	Rate per month Quoted by Contractor (Rs in Figure & Words)
1.	Maintenance of complete sewerage system of Berkhera N'hood as described in scope of work given below by deploying adequate man power with all required tools & tackles such as cleaning rods, rope, tasla, panjar, buckets etc. complete as per direction of the Engineer In-charge. Piplani - 34% Berkhera - 28% Govindpura - 24% Habibganj - 14%	One x 15 Months	76904.67	

Scope Of Work - - - Regarding

The scope of work for carrying out aforesaid work as per direction of the Engineer In-charge includes following activities as per details given below :

1. Removal & clearing of chockages from WC's including clearing all connecting sewer lines, house chambers etc. as per requirement and removal of the debris to a distance up to 50 meters etc. complete to the satisfaction of the Engineer In-charge.
2. Removal & clearing of chockages from Nahani Trap, Gully Trap including clearing all connecting sewer lines, house chambers etc. as per requirement and removal of the debris to a distance up to 50 meters etc. complete to the satisfaction of the Engineer in-charge.
3. Removal / clearing chockages with de-silting of manholes of all size & depth on sewer line of different diameters i.e from 4" dia. to 14" dia. including clearing chockages of sewer line between two successive manholes where chockage is suspected for ensuring free flow of sewage and including disposal of debris to a distance up to 50 meters or part there of etc. complete to the satisfaction of the Engineer In-charge.
4. Removal & clearing of chockages from Wash Basin and or Sink including removal and refitting of waste pipe wherever required and removal of the debris to a distance up to 50 meters etc. complete to the satisfaction of the Engineer In-charge.
5. Clearing, Desilting and Flushing of main trunk sewer line of diameter more then 14" and up to 36" diameter at all depth, once in a year and as & when required, by way of rodding, rope pulling and by any other required means including clearing on line manholes and removal of debris to a distance up to 50 meters or part there of etc. complete to the satisfaction of the Engineer In-charge. [The required water for flushing shall be made available by the department free of cost]

SIGNATURE OF CONTRACTOR

SIGNATURE OF OFFICER