

SCHEDULE 'A'**Annexure: I****Name of work : Repair and improvement work for clear water reservoir at Water Treatment Plant, Jail Hill.**

S.No	It. Code	Description of items	Qty.	Unit	Rate	Amount
1	15.2	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 metres lead:				
	15.2.1	1:3:6 or richer mix.	130.00	CUM	368.45	47898.50
2	2.26	Extra for every additional lift of 1.5 m or part thereof in :				
	2.26.1	All kinds of soil	130.00	cum	18.90	2457.00
3	1.2.1	Carriage of material by manual labour including loading, unloading and stacking for lead less than 0.5 km lime, moorum, building rubbish.	130.00	cum	34.08	4430.40
4	15.17.2	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	2000.00	Kg	0.35	700.00
5	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 m lead.	500.00	SQM	8.20	4100.00
6	4.1.3	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level. 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	50.00	Cum	1584.89	79244.50
7	5.1	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work upto plinth level.				
	5.1.3	1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	315.00	Cum	1687.04	531417.60
8	12.21	Providing gola 75x75 mm in cement concrete 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 10 mm and down gauge) including finishing with cement mortar 1 : 3 (1 cement : 3 fine sand) as per standard design:				
	12.21.1	In 75 x 75 mm deep chase	145.00	MTR.	51.15	7416.75
9	5.28	Providing and fixing in position 12mm thick bitumen impregnated fibre board conforming to IS: 1838 including cost of primer, sealing compound in expansion joints.	1300.00	per cm depth per 100m	334.55	4349.15
10	RA	Labour for reinforcement for RCC work i/c straightening, cutting, bending, placing in position and binding all complete excluding cost of reinforcement but i/c cost of binding wire 18 gauge.	2000.00	Kg	6.35	12700.00
11	5.9.1	Centring and shuttering including strutting, propping, etc. and removal of form for: Foundations, footings, bases of columns, etc. for mass concrete.	150.00	SQM	119.25	17887.50
12	4.12	Extra for providing and mixing water proofing material in cement concrete work @ 1 kg per 50kg of cement.	2380.00	per bag of 50 kg cement	27.45	65331.00
13	13.18	Neat cement punning.	1255.00	SQM	9.90	12424.50
14	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:	1000.00	Kg	46.35	46350.00
15	7.7	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with :-				
	7.7.1	Cement mortar 1:6 (1 cement : 6 coarse sand).	175.00	cum	1521.09	266190.75

16	7.8	Extra for coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level.	175.00	Cum	361.50	63262.50
----	-----	---	--------	-----	--------	----------

1166160.15

Percentage quoted by the Contractor	%	Above	Below	At Par
Percentage quoted by the Contractor in words				

Signature of Contractor

Signature of Officer