

SCHEDULE 'A'**Annexure: I****Name of work : Provision of open drain from Gate No. 9 to main road Govindpura in Township.**

S.No	It. Code	Description of items	Qty.	Unit	Rate	Amount
1	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1	All kinds of soil.	1150.00	cum	103.40	118910.00
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:				
(i)	4.1.10	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size).	252.00	cum	1558.27	392684.04
(ii)	4.1.3	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	27.00	cum	1584.89	42792.03
3	1.1.2	Transportation of following material including loading, unloading and stacking if necessary etc. lead upto 2 km of building rubbish.	910.00	cum	56.41	51333.10
4	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations, etc. in layers not exceeding 20 cm in depth : consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5m	236.00	cum	45.70	10785.20
5	7.7	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with :-				
	7.7.1	Cement mortar 1:6 (1 cement : 6 coarse sand).	830.00	cum	1521.09	1262504.70
6	13.33	Pointing on stone work with cement mortar 1 : 3 (1 cement : 3 fine sand):				
	13.33.1	Flush / Ruled pointing.	1900.00	sqm	56.38	107122.00
7	4.11	Providing and laying damp-proof Course 50 mm thick with cement concrete 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	850.00	sqm	94.42	80257.00
						2066388.07

Percentage quoted by the Contractor	%	Above	Below	At Par
Percentage quoted by the Contractor in words				

Signature of Contractor

Signature of Officer